

Cost: Assume no access dredging. Based on the estimate for the Capoli Slough project in pool 9, the cost of rock/log islands is approximately \$240 per foot. Approximately 55 cubic feet or 2.95 tons of rock needs to be Placed on a 40 foot long tree with a 2 foot base diameter.